



Notes:

Plywood = 3/4 inch Thick
All joints made with biscuits
Dacron Hollofil II Fiber
Stuffing Density = 0.25 lb/ft**3
Stuff top of cabinet only
Port Diameter = 4.0 inches
Port length = 5.0 to 6.0 inches
Cabinet 1st mode ~ 32 to 34 Hz
All dimensions are in inches
Inside dimensions shown

Two I/4 inch terminal holes